



Toase-ehe Park Sanati Gohar Ofogh  
Petrochemical Co.  
**CONCEPTUAL, BASIC and DETAIL DESIGN  
ENGINEERING OF STYRENE PARK OFFSITE**



Document Title: Skid Foundation Plan

Document No.: EI027-HSE-VD – CI– DWG– 001 - R0

Rev. R0

Page 1 of 5

# STYRENE PARK OFFSITE

**Document Title:**

**Skid Foundation Plan**

Rev.	Issued Date	DESCRIPTION	PREPARED	CHECKED	APPROVED
R0	27-08-2024	IFA	F.sh	M.O	A.M



Toase-e Park Sanati Gohar Ofogh  
Petrochemical Co.  
**CONCEPTUAL, BASIC and DETAIL DESIGN  
ENGINEERING OF STYRENE PARK OFFSITE**



Document Title: Skid Foundation Plan

Document No.: EI027-HSE-VD – CI– DWG– 001 - R0

Rev. R0

Page 2 of 5


**REVISION RECORD SHEET**

Page Page	Revisions							Page	Revisions						
	R0	R1	R2	R3	R4	R5	R6		R0	R1	R2	R3	R4	R5	R6
1	X							41							
2	X							42							
3	X							43							
4	X							44							
5	X							45							
6								46							
7								47							
8								48							
9								49							
10								50							
11								51							
12								52							
13								53							
14								54							
15								55							
16								56							
17								57							
18								58							
19								59							
20								60							
21								61							
22								62							
23								63							
24								64							
25								65							
26								66							
27								67							
28								68							
29								69							
30								70							
31								71							
32								72							
33								73							
34								74							
35								75							
36								76							
37								77							
38								78							
39								79							
40								80							

CENTER OF GRAVITY			
DESCRIPTION	X (MM)	Y (MM)	Z (MM)
CONDENSER	3131	1575	4000
VESSEL SKID	2217	1153	1045
COMPRESSOR SKID	790	450	860

WEIGHT		
DESCRIPTION	DRY WEIGHT (KG)	WET WEIGHT (KG)
CONDENSER	5600	6200
VESSEL SKID	6000	7000
COMPRESSOR SKID	3500	4500

- NOTES:
1. ALL DIMENSIONS ARE IN MM.
  2. ANCHOR HOLES TOLERANCES:  $\pm 0.13$  in ( $\pm 3.2$  mm).
  3. BEAM LOCATION TOLERANCES:  $\pm 0.13$  in ( $\pm 3.2$  mm).
  4. SKID FLATNESS SHALL BE 0.0625" (1.6 mm).
  5. SURFACE PREPARATION SHALL BE PER PROJECT PAINTING SPECIFICATION.
  6. FOR CONDENSER DYNAMIC & STATIC LOADS, REFER TO CONDENSER DRAWINGS.
  7. BEAM SIZE : W8 X 48#, MATERIAL - ASTM A572 OR EQUIVALENT.




TOP VIEW

REV.	STATUS	DATE	PURPOSE OF ISSUE	PREP.	CHKD.	APPD.	AUTH.
1	F	22.08.24	FOR APPROVAL	AJD	AJD	IES	SES
0	F	26.07.24	FOR APPROVAL	AJD	AJD	IES	SES

CLIENT:	PROPANE REFRIGERATION PACKAGE		
SERVICE:			
LOCATION:			
UNIT TAG NO.:	RU-001 AB		
VENDOR LOGO			
Contract No.	P.O. No.		
SCALE			
DRAWING TITLE:			
FOUNDATION DRAWING			
DRAWING NO.	REV.	SHEET No.	SIZE
	1	1 OF 2	D






CONDENSER TOP VIEW

REV.	STATUS	DATE	PURPOSE OF ISSUE	PREP.	CHKD.	APPD.	AUTH.
1	F	22.08.24	FOR APPROVAL	AJD	AJD	IES	SES
0	F	26.07.24	FOR APPROVAL	AJD	AJD	IES	SES

CLIENT:	PROPANE REFRIGERATION PACKAGE		
SERVICE:			
LOCATION:			
UNIT TAG NO.:	RU-0001 A/B		
VENDOR LOGO			
Contract No.	P.O. No.		
SCALE			
DRAWING TITLE:			
FOUNDATION DRAWING			
DRAWING NO.	REV.	SHEET No.	SIZE
	1	2 OF 2	D





FRONT VIEW  
CL. A-C

SIDE VIEW


FRONT VIEW  
CL. B

\* THIS DIMENSION WILL BE FINALIZED AFTER APPROVED OF MOTOR DATA SHEET




TOP VIEW


BASE PLATE VIEW




DET. M




SEC. A-A  
Thk.=25mm



DET. C



DET. B



DET. D

Table 1. Weight of equipments For 1 Units (Total Units = 2)

Equipment	Total No in one Unit	Total Weight in one Unit (tonf)	Total No. for One Bay	Weight for One Bay (kgf)
Bundle Frame	1	0.865	1	865
Tube Bundle & Headers	1	2.635	1	2635
Water in Tubes & Headers	1	0.48	1	480
Plenum	2	0.245	2	490
Fan Ring	2	0.13	2	260
Motor	2	0.07	2	140
Fan	2	0.0275	2	55
Speed Reducer	2	0.25	2	500
Machinery Mount	2	0.32	2	640
Fan Guard	2	0.0325	2	65
sum				2150
Fabrication Weight For 1 Units				5650
Operation Weight For 1 Units				6130
Hydrotest Weight For 1 Units				6130
Total Weight of Main structure, Ladder for 1 Units				6800

TABLE: Joint Reactions

Joint	OutputCase	Fx	Fy	Fz
Text	Text	Kgf	Kgf	Kgf
A-1	DEAD S	16.65	45	861.98
A-1	DEAD	49.34	-158.83	1640.14
A-1	DEAD OP	4.08	-14.37	92.37
A-1	DEAD N	-1631.93	429.16	-2881.5
A-1	LIVE	3.34	25.54	1383.73
A-1	WX	31.57	329.34	-352.72
A-1	WY	-387.76	93.94	-669.09
A-1	SNOW	9.74	-24.99	547.61
A-1	EQX	106.43	1146.34	-1764.17
A-1	EQY	-1561.76	337	-3289.21
A-1	EQXO	210.24	2295.43	-3529.78
A-1	EQYO	-3123.79	673.24	-6571.39
A-2	DEAD S	-20.6	1.599E+13	380.54
A-2	DEAD	-33.06	-0.0000289	811.07
A-2	DEAD OP	-0.21	-3.963E-07	55.27
A-2	DEAD N	-10.59	-1.13	-378.95
A-2	LIVE	-76.47	6.353E+13	402.18
A-2	WX	1.165E+12	49.87	8.288E+13
A-2	WY	-54.91	-1.269E+13	-353.83
A-2	SNOW	-19.58	-8.653E+07	221.21
A-2	EQX	0.004107	45.8	0.09216
A-2	EQY	-48.82	-0.38	-1465.12
A-2	EQXO	0.00889	92.7	0.18
A-2	EQYO	-98.54	-0.78	-2927.34
A-3	DEAD S	16.65	45	861.98
A-3	DEAD	49.34	158.83	1640.17
A-3	DEAD OP	4.08	14.37	92.37
A-3	DEAD N	39.17	235.02	482.86
A-3	LIVE	3.34	-25.54	1383.73
A-3	WX	-31.57	329.34	352.72
A-3	WY	387.76	-93.94	669.09
A-3	SNOW	9.74	24.99	547.61
A-3	EQX	-106.43	1146.49	1764.07
A-3	EQY	-1071.77	-428.48	-2570.23
A-3	EQXO	-210.36	2295.75	3529.6
A-3	EQYO	-2144	-856.2	-5134.3
B-1	DEAD S	34.11	-1.44	482.68
B-1	DEAD	174.23	-2.24	983.92
B-1	DEAD OP	16.3	0.03128	81.45
B-1	DEAD N	-670.87	1.33	2555.04
B-1	LIVE	-43.74	-6.51	64.14
B-1	WX	255.25	0.99	-374.63
B-1	WY	-1.33	-70.96	504.74
B-1	SNOW	24.65	-1.56	193.87
B-1	EQX	-985.73	4.1	-1834.5
B-1	EQY	-51.12	-28.6	2619.38
B-1	EQXO	-1968.03	8.18	-3658.39
B-1	EQYO	-102.38	-57.85	5233.15
B-2	DEAD S	-3.76E+15	-9.82	342.79
B-2	DEAD	-1.168E+10	-61.15	847.79
B-2	DEAD OP	-1.602E+11	-8.01	77.09
B-2	DEAD N	-0.0003857	-409.24	720.08
B-2	LIVE	8.844E+15	82.81	-147.91
B-2	WX	-56.07	3.583E+12	-6.399E+12
B-2	WY	-8.004E+14	-439.42	682.53
B-2	SNOW	-3.498E+11	3.21	131.34
B-2	EQX	0.02819	0.04229	-0.07544
B-2	EQY	0.006383	-1570.51	2804.88
B-2	EQXO	-0.2	0.08416	-0.15
B-2	EQYO	0.0007535	-3138.25	5603.81
B-3	DEAD S	-34.11	-1.44	482.68
B-3	DEAD	174.23	-2.24	983.9
B-3	DEAD OP	-16.3	0.03128	81.45
B-3	DEAD N	-670.07	1.26	1104.47
B-3	LIVE	43.74	-6.51	64.14
B-3	WX	-255.25	-0.99	374.63
B-3	WY	1.33	-70.96	504.74
B-3	SNOW	-24.65	-1.56	193.87
B-3	EQX	-985.8	-4.09	1834.58
B-3	EQY	-40.75	-28.68	1900.29
B-3	EQXO	-1968.16	-8.15	3658.54
B-3	EQYO	-81.36	-57.83	3796.07

GENERAL DATA

ITEM NO. -

DESIGN CODE BUNDLE/STRUCTURE ASME SEC.VIII DIV.1(2019), AP1661(2013-7th EDITION)/Standard No. 2800

INLET PRESSURE/PRESSURE HRO. (ALLOWABLE/CALC) 19.8 Bar / (0.1/0.016) Bar

DESIGN PRESSURE 22+F.V. (barg)

HYDROSTATIC TEST PRESSURE 28.6 (bar)

TEMPERATURE IN/OUT(TUBE SIDE) 73.5°C/56.32°C

DESIGN TEMPERATURE 120 °C

MINIMUM DESIGN METAL TEMPERATURE -45°C

AIR INLET/OUTLET TEMPERATURE (AIR SIDE) 48 / 52.28 °C

MINIMUM DESIGN AMBIENT TEMPERATURE 5 °C

CORROSION ALLOWANCE 3 mm

ULTRASONIC TEST YES(Full)[See note 8]

RADIOGRAPHY YES(Full)[See note 8]

STRESS RELIEVING YES

BARE/FINNED SURFACE PER UNIT 68.101/1579.2 m2

NUMBER OF BUNDLE PER BAY 1

NUMBER OF UNIT 2

NUMBER OF BAY PER UNIT 1

NOZZLE SIZE(INLET/OUTLET/RATING/TYP) 1x4"/1x2"/SCH.160/#300

PROCESS FLUID NAME PROPANE

SERVICE PROPANE

PASSES PER BUNDLE 4

FINNED-TUBES/BUNDLE NO.140 TUBES,OD=25.4,SEAMLESS MIN.W.#G1.6,THK=1.65,1-6096 mm

Tube to tube sheet joint STRENGTH WELD + EXPANDED

Fin (Type,material, OD,FPF) EXTRUDEAL 1060,57,15.11

STEAM COIL No

LOUVER/TYP NO/-

PLENUM / FAN RING FORCED TYPE/CONICAL L/D=0.05

VIBRATION SWITCH YES(FOR EACH FAN) MANUAL & ELECTRIC RESIST

FAN SPECIFICATION RPM/DIAMETER 382/7 Ft

Pitch angle (for fan) 8.5°

BLADE NO. / MATERIAL 4/ALUMINIUM

AIR QUANTITY FOR FAN 26.879 m3/S

STATIC PRESSURE 102.95 Pa

TEMPERATURE IN/OUT 48°C/52.28°C

SPEED REDUCER TYPE V BELT

REDUCTION RATIO 3.76

MOTOR TYPE ELECTRIC-Exe.IIB-T3-IP55

VOLTAGE/Freq./PHASE 400/50/3

RPM/KW 1500/7.5 Kw

Motor VFD per unit 50%

S.P.L. 1m all side of fan: <85 dB(A)1m all sides

- NOTES:
- Loading Data  
WIND :ASCE7-16,VELOCITY :125km/h, EXPOSURE : C  
Earthquake: Standard No. 2800,A=0.3,B=2.75,I=1.4,R=3.5,SOIL TYPE=IV
  - Fans  
-100% AP(Adjustable pitch-manual)
  - Miscellaneous  
- The Inlet Header Boxes Are Fixed In The Direction Of Fin Tubes,  
Refer To Table For The Lateral Displacement In Y Direction  
- Flange Face Detail : ASME ANSI B16.5
  - All Dimensions Are In Millimeter Unless Otherwise Specified.
  - All Dimensions Tolerances Are According to API 661.(Figure 10)
  - Bolts which are used for fixing headers to side frame , on sliding side should be removed after erection.
  - PROTECTION(SEE Galvanizing Specification and Inspection Procedure: EI027-DMF-VD-QC-PRO-024
  - RADIOGRAPHIC TEST (FULL/SPOT) SHALL BE IN COMPLIANCE WITH THE REQUIREMENTS OFASME SEC. VIII DIV.1 UW-11 & UW-12.
  - 50% motors per unit to be VFD.


LOAD DEFINITION\*

LOAD	DESCRIPTION
DEAD	DEAD LOAD(PLENUMS+FAN RINGS+FAN GUARDS+FAN+MOTOR+SPEED REDUCERS+GRATING+TUBE BUNDLE EMPTY)+HEADER WALK WAY
DEAD OP	WEIGHT OF LIQUID WITHIN EACH TUBE BUNDLE& STEAM COIL(WATER)
DEAD S	SELF WEIGHT OF STRUCTURE
DEAD N	NOZZEL LOAD
LIVE	WALKWAY LOAD 250 Kg/m2
EQX	SEISMIC LOAD DIR.X
EQY	SEISMIC LOAD DIR.Y
WX	WIND LOAD DIR.X
WY	WIND LOAD DIR.Y
SNOW	66 Kg/m2

\* Further Definition Check the Steel Structure Calculation.Doc No.: EI027-DMF-VD-ST-CAL-004  
1158-A01-0030-00

THE MAXIMUM ALLOWABLE MOMENTS AND FORCES PER EACH NOZZLE (IF LOADS ARE DIVIDED EQUALLY FOR NOZZLES ACCORDING TO 3xAPI 661(7.1.10.1)

SIZE	Fx(N)	Fy(N)	Fz(N)	Mx(N.m)	My(N.m)	Mz(N.m)
4"	10020	8010	10020	2430	3660	2430
2"	3060	3990	3060	450	720	450



CONNECTIONS

NO.	REP.	QTY. PER BAY/UNIT	DIA	DESIGNATION
N1	INLET NOZZLE/FLANGE	1/2	4"	FLANGE ANSI B16.5,#300,MIN.PRESSURE 19.8 BAR,SA-350 LF2 CL1,THK=13.9
N2	OUTLET NOZZLE/FLANGE	1/2	2"	FLANGE ANSI B16.5,#300,SCH.160,MIN.PRESSURE 19.8 BAR,SA-350 LF2 CL1,THK=16.6
V1&V2	VENT	2/4	1"	FLANGE ANSI B16.5,#300,LWN,SA-350 LF2 CL1,THK=14.3
D1&D2	DRAIN	2/4	1"	FLANGE ANSI B16.5,#300,LWN,SA-350 LF2 CL1,THK=14.3
1A	VIBRATION SWITCH	2/4	-	SEE FAN DRIVE ASSEMBLY DRAWING
2A	MOTOR(7.5Kw)	2/4	-	SEE FAN DRIVE ASSEMBLY DRAWING
3A	FAN	2/4	7ft	SEE FAN DRIVE ASSEMBLY DRAWING

LATERAL DISPLACEMENT OF HEADERS (DIRECTION X) INSIDE BUNDLE FRAME IN RELATION WITH EXPANSION FORCES ON NOZZLES (mm) (ACCORDING TO API661 7-1-1-2)

MAXIMUM DISPLACEMENT INLET/OUTLET : ±9

\* FOR MORE DETAILS FOR EACH COMPONENT OF AIR COOLER REFER TO BELOW DRAWING & DOCUMENTS.

REFERENCED DWG&DOC.

TITLE	VENDOR DOCUMENT NO.	CLIENT DOCUMENT NO.
Tube Bundle Drawing	1158-A01-2000-00	EI027-DMF-VD-ME-DWG-025
Bundle Frame Drawing	1158-A01-2400-00	EI027-DMF-VD-ME-DWG-007
Fan Drive Assembly Drawing	1158-A01-6000-00	EI027-DMF-VD-ME-DWG-008
Fan Ring Drawing	1158-A01-5067-00	EI027-DMF-VD-ME-DWG-009
Support Mechanism Drawing	1158-A01-5167-00	EI027-DMF-VD-ME-DWG-010
Plenum Drawing	1158-A01-6307-00	EI027-DMF-VD-ME-DWG-011
Steel Structure Drawing	1158-A01-1100-00	EI027-DMF-VD-ST-DWG-013
Header Walkway Drawing	1158-A01-1200-00	EI027-DMF-VD-ST-DWG-014
Ladder Drawing	1158-A01-1920-00	EI027-DMF-VD-ST-DWG-015
Surface Preparation and Painting Procedure for Air Cooler	1158-A01-Q501-00	EI027-DMF-VD-QC-PRO-024

REV	DATE	DESCRIPTION	DRAWN BY	CHECKED BY	APPROVED BY	FINAL APPROVED BY
R3	08/21/2024	ISSUED FOR APPROVAL	F.SZ	J.M.	J.B.L.	A.GHZ
R2	08/10/2024	ISSUED FOR APPROVAL	F.SZ	J.M.	J.B.L.	A.GHZ
R1	07/22/2024	ISSUED FOR APPROVAL	F.SZ	J.M.	J.B.L.	A.GHZ
RO	06/30/2024	ISSUED FOR APPROVAL	F.SZ	J.M.	J.B.L.	A.GHZ

PROJECT: AIR COOLER FOR Toase-che Park Sanati Gohar Ofogh Petrochemical Co.

General Arrangement Drawing  
1158-A01-1000-00

DWG. NO. \_\_\_\_\_

SCALE: N.T.S. SIZE: A1 REV.: R3